







Bureau of Waterways Engineering and Wetlands

DGS 184-22 Meadow Brook Flood Control Project, Phase 3

Meadow Brook
City of Scranton
Lackawanna County

June 26, 2024

Project Partners

- Department of General Services (DGS)
 - * Funding Agency
 - * Contract Administrator
- Department of Environmental Protection (DEP)
 - * Program Agency (the funds user)
 - * Issue DEP Permit
- Reilly Associates
 - * Design Professional
- City of Scranton
 - * Project Sponsor



Responsibilities of Project Partners

DGS

- * Request Budget Office to release design funds
- * Select Design Engineer (Reilly)
- * Conduct legal review and approval of all land acquisition and conveyance documents
- * Review and approve construction plans and specifications
- * Request Budget Office to release construction funds
- * Bid, award, and administer construction contract



Responsibilities (cont.)

DEP

- * Provide engineering review & guidance to Reilly
- * Issue DEP permits
- * Review City's land acquisition documents
- * Assist City in coordinating major utility relocations
- * Provide Construction Inspection Services during construction
- * Transfer Permit to City after project completion
- * Provide LOMR application information to City for FIS map revision
- * Issue Operation and Maintenance Manual to City
- * Conduct Annual Operation and Maintenance Inspections



Responsibilities (cont.)

Reilly Associates

- * Design project, develop contract drawings and specifications, and obtain all permits and approvals
- * Assist City in coordinating major utility relocations
- * Develop land acquisition documents for the City
- * Provide Engineering and Construction Management Services during construction





Responsibilities (cont.)

City of Scranton

- * Execute Sponsorship Agreement with DEP
- * Fund City's project related costs
- * Obtain easements for construction and maintenance (Obtain signatures and record deeds)
- * Coordinate and complete Sponsor Adjustments
- * Provide DEP with \$42,000 Performance Security. Establish a Maintenance Escrow Account and Deposit \$14,000 annually into the account.
- * Operate and Maintain the completed Project
- * Participate in annual maintenance inspections



Project Authorization & Funding

- Flood control projects are authorized and funded by the Commonwealth of Pennsylvania. No Federal Funding. Project Sponsor also contributes.
- Total Construction Estimate: \$12,100,000



Design Completion & Construction Timeline

- Interim Construction Document Phase* July 2024
- Construction Documents Phase* August 2024
- Right-of-Way Acquisition* March 2025
- Construction Contract Bid Advertisement* June 2025
- Project Construction Phase* November 2025 through May 2027





Definitions

- 1% Annual Storm: A storm event that has a 1% chance of occurring in any given year.
- Permanent Easement: Permanent easement grants right of ingress, egress, and regress to construct and maintain project (10-15 feet beyond edge of culvert or outside edge of floodwall).
- Temporary Easement: Temporary right-of-way used during construction solely for the purpose of constructing project. Reverts back to property owner when construction is complete.
- Sponsor Adjustments: The relocation and/or removal of any utility line, structure, shed, playground, fence, pool, etc., that will interfere with construction of the project (City cost).



Previously Completed Phase






- Trash Rack
- 7' Reinforced Concrete Pipe
- 7'W x 7'HConcreteU-Channel
- 7'W x 7' HConcreteBox Culvert

Total Project Length 2,400 Feet


























Existing culvert near Delaware Street






Existing culvert near Delaware Street





Project Features

- Begin project upstream of Electric Street in Dunmore Borough
- Proposed Trash Rack at culvert entrance
- 7-foot diameter Concrete Pipe approximately 1780 feet
- 7-foot x 7-foot Concrete U-channel approximately 150 feet long
- 7-foot x 7-foot Box Culvert approximately 430 feet long
- Tie into where the DGS 184-22 Phase 2 construction ended (near Green Ridge Street and Penn Avenue)
- Total Project Length 2,400 Feet









CURVE DATA									
CURVE	P.I. COORDINATES				_	-		P.C.	P,T,
NO.	NORTH	EAST	Δ.	, u	16		١.	STATION	STATION
PJ. #1	467,023.1	2,546,824.8	25'-00'-00"						

SPONSOR ADJUSTMENTS

	DESCRIPTION	LOCATION			
NO.		€ STATION	OFFSET	ADJUSTMENT REQUIRED	
SA2-1	FENCE	14+82 TO 16+00	LT./RT.	REMOVE AND REPLACE	
SA2-2	ELECTRIC ST. CURBS	15+55 TO 15+86	LT./RT.	REPLACE	
SA2-3	ELECTRIC ST. SIDEWALK	15+40 10 15+84	LT./RT.	REPLACE	
SA2-4	ELECTRIC ST. PAVING	15+56 TO 16+00	LT./RT.	REPLACE	


CONTRACTOR ADJUSTMENTS


NO.	DESCRIPTION	LOCA:	TION	ADJUSTMENT REQUIRED
NO.	DESCRIPTION	& STATION	OFFSET	ADJOSIMENT RECORED
CA2-1	TRASH RACK	13+20 TO 13+34	RT	REMOVE
CA2-2	DELETED			
CA2-3	4" GAS LINE	15+95	E	PROTECT AND SUPPORT
CA2-4	CONCRETE BOX CULVERT	15+43 TO 16+40	ě.	REMOVE


SPONSOR ADJUSTMENTS - BY OTHERS

	NO.	DESCRIPTION	LOCA.	TION			
			€ STATION	OFFSET	ADJUSTMENT REQUIRED		
	SA2-5	20" WATER LINE	15+92	٤	RELOCATE		

AS BUILT REVISIONS PROFESSIONAL - RELLY ASSOCIATES Professional's Signature Date REILLY ASSOCIATES CONSULTING ENGINEERS
49 SOUTH MAIN STREET, SUITE 200
PITTSTON PENNSYLVANIA 18840 COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES HARRISBURG, PENNSYLVANIA PROJECT NO. DGS 0184-0022 PHASE 3 MEADOW BROOK FLOOD CONTROL CITY OF SCRANTON LACKAWANNA COUNTY, PENNSYLVANIA PLAN AND PROFILE STA. 12+90 TO STA. 16+00 05/31/24 CM AS SHOWN MAM







	CURVE_DATA									
Γ	CURVE		RDINATES	Δ.	D	R	T	L	P.C.	P.T.
L	NO.	NORTH	EAST	-					STATION	STATION
	PJ. #12	466,950.7	2,545,855.2	2'-18'-18"	05'-43'-47"	1000.00'	20.12"	40.23	26+33.88	26+74,11
	PJ. #13	466,981.2	2,545,803.2	28"-00"-00"						
	PJ. #14	466,981.7	2,545,791.5	28"-00"-00"						
	PJ. #15	466,976.8	2,545,781.1	28'-00'-00"						


	SPÓNSÓF	ADJUSTMENTS		
NO.	DESCRIPTION	LOCATION		ADJUSTMENT REQUIRED
NO.	DESCRIPTION	€ STATION	OFFSET	ADJUSTMENT REQUIRED
SA5-1	WYOMING AVE. PAVING	25+93 TO 26+39	LT./RT.	REPLACE
SA5-3	WYOMING AVE. CURBS	25+93 TO 26+39	LT./RT.	REPLACE
SA5-5	PAVED DRIVE	26+39 TO 27+54	LT./RT.	REPLACE
SA5-6	WYOMING AVE. SIDEWALK	25+93 TO 26+39	LT./RT.	REPLACE
SA5-7	RETAINING WALL	26+46 TO 27+15	RT.	REPLACE
SA5-8	SWNG SET	27+38	RT.	REMOVE AND REPLACE
SA5-9	PAVED DRIVE	27+75 TO 28+00	LT./RT.	REPLACE
SA5-10	CONCRETE SIDEWALK		£	REPLACE
SA5-11	SUNSET ST. CONCRETE CURB		٤	REPLACE
SA5-12	YARD DRAIN		£	EXTEND PIPE TO PROPOSED CULVERT


CONTRACTOR ADJUSTMENTS


NO.	DESCRIPTION	LOCA	TION	ADJUSTMENT REQUIRED
NO.	DESCRIPTION	€ STATION	OFFSET	ADJUSTMENT REQUIRED
CA5-1	2" GAS LINE	26+15	£	PROTECT AND SUPPORT
CA5-2	COMMUNICATION LINES	26+22	£	PROTECT
CA5-3	COMMUNICATION LINES	26+30	£	PROTECT
CA5-4	#1729 WYOMING AVENUE	27+00	LT.	UNDERPIN OR SUPPORT AS NECESSARY TO ENSURE STRUCTURAL INTEGRITY
CA5-5	#1733 WYOMING AVENUE	27+00	RT.	UNDERPIN OR SUPPORT AS NECESSARY TO ENSURE STRUCTURAL INTEGRITY
CA5-6	UTILITY POLE	27+38	RT.	PROTECT AND SUPPORT
CA5-7	CONCRETE/STONE BOX CULVERT	25+67 TO 26+06	RT.	REMOVE AND BACKFILL
CA5-8	CONCRETE/STONE BOX CULVERT	26+06 TO 27+18	VARIES	REMOVE
CA5-9	CONCRETE/METAL BOX CULVERT	27+18 10 29+00	VARIES	REMOVE


SPONSOR ADJUSTMENTS-BY OTHERS								
NO.	DESCRIPTION	LOCA	TIÓN	ADJUSTMENT REQUIRED				
NO.		€ STATION	OFFSET	ADJUSTMENT REQUIRED				
SA5-2	6" SANITARY LINE	25+99	Æ	RELOCATE				
SA5-4	6" WATER LINE	26+10	£	RELOCATE				


















Cross Section








Cross Section 15+00



ENGINEERING / ENVIRONMENTAL / SURVEYING






Cross Section



ENGINEERING / ENVIRONMENTAL / SURVEYING






Cross Section









Cross Section



ENGINEERING / ENVIRONMENTAL / SURVEYING






Cross Section 22+00









Cross Section



ENGINEERING / ENVIRONMENTAL / SURVEYING






Cross Section 30+00








Cross Section








ENGINEERING / ENVIRONMENTAL / SURVEYING






Cross Section



ENGINEERING / ENVIRONMENTAL / SURVEYING



(Fnd)

Cross Section



ENGINEERING / ENVIRONMENTAL / SURVEYING

ROADWAY PAVE

2'-0"

CA8-1

8" WATER SA8-3

COMPACTED

BACKFILL

SA8-2

Current Design Status

- Permits
 - DEP Water Obstruction Permit –Under Review
 - NPDES Permit Application Ready for submission
 - PennDOT Temporary Access Highway Occupancy Permit Approved.
- Interim Construction Document Phase
 - Under Review by DGS & DEP
 - Expected Completion July 2024
- Final Construction Documents
 - Expected Completion August 2024
- Right-of-Way Acquisition
 - Expected Completion March 2025
- Construction Contract Bid Advertisement
 - June 2025
- Project Construction Phase
 - November 2025 May 2027



Questions and Comments

Department of General Services (DGS)

Adam Paul

717-787-7667

apaul@pa.gov

Department of Environmental Protection (DEP)

Shane Erdman

717-772-0434

shanerdman@pa.gov

Reilly Associates

Martin Musso

570-654-2473

mmusso@reillyengineering.com

City of Scranton

Morgan Fetsock

570-504-4943

mfetsock@scrantonpa.gov

