McLAIN / ROCKWELL AVENUE PARK IMPROVEMENTS - 2021 PHASE III BID FORM (1-7-22)

In accordance with the Bidding and Contract Documents, the undersigned proposes to perform the Work, furnish all materials and complete the Work in its entirety in the manner and under the conditions required at the prices listed as follows:

Section 1 - GENERAL CONDITIONS									
Item #	Line Item Description	Quantity & U	Inits	Unit Cost	Extended Cost				
1-1	Insurance and Bonding	1	LS						
1-2	Mobilization/Demobilization	1	LS						
			Total :	\$					
Section 2 - SITE DEMOLITION/E&S									
Item #	Line Item Description	Quantity & U	Inits	Unit Cost	Extended Cost				
2-1	Remove/Dispose of existing basketball court asphalt; bench, backboards/rims (poles to remain)	1	LS						
2-2	E&S Controls (12" compost filter sock, temporary fencing for LOD, RCE)	1	LS						
		Total Section 2 Bid			\$				
Soctio	n 3 - SITE IMPROVEMENTS								
Item #	Line Item Description	Quantity &	Units	Unit Cost	Extended Cost				
3-1	Basketball Backboard and Rims; complete (use existing poles, installation; equipment supplied by City)	1	LS						
3-2	Basketball Court Asphalt; full-depth asphalt, complete in-place	460	SY						
3-3	Basketball Court Color Coat Package; complete (furnish & install, acrylic resurfacer, color coat layer, line striping)	460	SY						
3-4	Basketball Pole Restoration; complete (clean posts, paint posts, black)	1	LS						
3-5	Lawn Restoration - Topsoil (2" depth), seed, mulch fertilizer; complete; all site disturbance areas	1	LS						
3-6	Conversion of pea gravel area to skinned infield, as noted	1	LS						
3-7	Bike Racks with Concrete Pads; complete (equipment supplied by City)	2	EA						
3-8	Concrete Walkway to basketball court; complete (4" depth concrete with 2B subbase, match existing finish)	1	LS						
	\$								

TOTAL BASE BID (Sections 1-3) \$

ADD /	' ALT #1				
Item #	Line Item Description	Quantity & U	nits	Unit Cost	Extended Cost
A-1	Parking Lot Asphalt (16 new stalls); full-depth asphalt, complete in- place	545	SY		
A-2	Baseball Field ADA Stalls (2 new stalls); full-depth concrete, complete in- place; line striping, signage	1	LS		

COMPANY PROVIDING BID: